

air barrier

**abaa**

association of  
america

**CONFERENCE  
& TRADE SHOW**

**MAY 8-9**

**2018**

**SALT LAKE**

**CITY**

**AIR BARRIER EDUCATION TRACKS FOR  
THE CONSTRUCTION INDUSTRY**

# **Quality Management Best Practices for Installing Self-Adhering Sheet Air Barriers**

**Chris Bubser, AIA, LEED AP BD+C**

*Mortenson Construction*



Air Barrier Association of America (ABAA) is a Registered Provider with The American Institute of Architects Continuing Education Systems. Credit earned on completion of this program will be reported to CES Records for AIA members. Certificates of Completion for non-AIA members are available on request.

This program is registered with the AIA/CES for continuing professional education. As such, it does not include content that may be deemed or construed to be an approval or endorsement by the AIA of any material of construction or any method or manner of handling, using, distributing, or dealing in any material or product.



# Quality Management Best Practices for Installing Self-Adhering Sheet Air Barriers

## Learning Objectives:

1. Identify best practices and lessons learned during the installation of air barrier system on a large commercial building
2. Demonstrate how a QA/QC process can reduce the inherent risk in to control water, air, and vapor
3. Describe the methods used to control and assure the quality of the barrier system from design through construction
4. Explore how the testing of adjacent enclosure systems can impact inspection of the air barrier

# Agenda

## Introduce Quality Management Program

- Quality Core and the Project Quality Plan
- Definable Feature of Work Log
- Compare with Building Enclosure Commissioning and Assurance Program

## Case Study Project


- Wall Construction
- NFPA 285
- Design Review
- Enclosure Review

## Inspections and Testing


## Summary



# Goals for Quality Management Program



# Strategies: Project Quality Plan (PQP)



# Definable Feature of Work (DFW)

## Phase Level



### Design Review

Drawing and Specification Review

Coordination

Mockups

Change Management

### Constructability Review

Enclosure Coordination Meetings

## Task Level (Work Feature)



### Preparatory Meeting

Change Management

### Integrated Work Plan

### Initial Inspection

Quality Management

### Final Inspection

# Definable Feature of Work (DFW)

Title	IWP Required (blank = No)	Prep Meeting/ IWP Review	Anticipated Start Date	Initial Inspection	Mock-Up Required (blank = No)	Quality Control Notes (Mock-up Description, Performance Testing, 3rd Party Inspections, etc.)
<b>General Conditions</b>						
Special Inspections & Testing - Structural & Technical		11/8/15	11/15/15	N/A		
Tower Cranes Erection	Y	2/1/16	2/8/16	2/9/16		3rd Party Inspection
Personel/Material Hoist		Scheduled 7/29	8/1/16	8/2/16		3rd Party Inspection
Earth Retention Systems	Y	DONE	1/20/16	1/21/16		3rd Party Design Review and Inspection Mort Inspection
<b>Existing Conditions</b>						
Hazardous Material Abatement	Y	DONE	1/20/16	NA		IWP received 1/20
Demolition	Y	11/6/15	11/13/15	NA		
Erosion Control		11/23/15	11/30/15	12/1/15		Subcontractor weekly (or 1/2" of rainfall within 24 hrs)
<b>Sitework</b>						
Utilities	Y	NOT DONE	4/29/16	4/30/16		
Landscaping and Hardscaping, Irrigation, Site Furnishings		6/7/17	6/14/17	6/15/17		
Storm water infiltration system		5/8/17	5/15/17	5/16/17		
<b>Foundation</b>						
Footings and Grade Beams	Y	1/25/16	2/1/16	2/2/16		Prepour (Soil, Formwork, Rebar, Embeds/Sleeves, Mix, Design, Install Method/rate)
Backfill and compaction		DONE	4/1/16	4/2/16	Y	In Place Mock-up, collect and save 3rd party soils inspection/tests
<b>Structure</b>						
CMU		DONE 7/25/16	8/8/16	8/9/16		
Mortenson Self-Perform Concrete (footings, foundation walls, columns)	Y	DONE	2/3/16	2/4/16		Includes Tunnel, Winter Conditions, Columns, Interaction with WP membrane,
Mortenson / CECO Self-Perform Concrete decks	Y	3/21/16	3/28/16	3/29/16		Includes Winter Conditions, PT, Shoring
Structural Steel Erection	Y	9/6/16	9/13/16	9/14/16		Date is for start of skyway erection. Includes metal decking installation, as-built specific points after erection
Mortenson Self-Perform Slab on Metal Deck	Y	9/13/16	9/20/16	9/21/16		Date is for skyway floor. Includes floor flatness discussion, as-built specific points after pours
Precast Architectural Concrete	Y	DONE 7/25/16	8/8/16	8/9/16	Y	
<b>Enclosure</b>						
Foundation Waterproofing	Y	DONE	3/15/16	3/16/16	Y	Includes flexible flashings, sheet metal flashings, water-resistive barriers (WRBs), preformed joint seals,
Exterior wall framing, sheathing and waterproofing above grade (WRB)		DONE 6/6/16	8/1/16	8/2/16		Includes mineral wool insulation (on exterior walls)
Roofing, Deck Insulation, and roof accessories		9/22/16	9/29/16	9/30/16		
Metal Wall Panels		9/8/16	9/15/16	9/16/16	Y	Includes Louvers
<b>Openings (Doors and Windows)</b>						
Hollow metal doors and frames, wood doors, door hardware, sliding interior doors, etc.		10/11/16	10/18/16	10/19/16		Be sure to cover security / access control.
Curtainwall and Glazed Assemblies, Entrances and Storefronts	Y	8/30/16	9/6/16	9/7/16	Y	Include firestopping at slab edge

Phase Level

Task Level



BECx	Case Study	ABAA QAP	
Owner's Project Requirements (OPR)	Design Narrative	No	Design Narrative includes some of this information, but OPR document has more specific information like Owner directives, restrictions or limitations, durability expectations and building enclosure life to have more detail relating directly to enclosure systems.
Drawing and Specification Review	Yes	No	In BECx, checking for inclusion of Commissioning Process requirements In Case Study, checking coordination and constructibility
Building Enclosure Specialist	On-Site Quality Manager	ABAA Accredited Contractor Certified Installer	On-site QM is building enclosure SME, but is employee of GC
Commissioning Authority	No	No	
Third Party Reviewer, Inspectors	Yes	Yes	
Commissioning Plan	Project Quality Plan	Specifications with ABAA QAP	
BECx Progress Reports	Inspectors reports Third Party Reviewer reports	Inspectors reports Third Party Reviewer reports	
Basis of Design reviews at design phase	No	No	Some other projects (usually Design Building delivery method) include periodic design review by GC
Technical Peer Review of enclosure	Enclosure Review by GC and Third Party	No	
Thermal Analysis	By Consultant and by GC's in-house Performance	No	
Review and advise lab and field mockups	By Third Party Reviewer	Yes	
BECx reviews submittals	GC reviews submittals	No	
Issues/non-conformance log	Yes		
Construction observation	By Third Party Reviewer and Architect	By Third Party Reviewer	
Pre-construction meeting	Yes	Yes	
BECx activities in project schedule	No	No	
Site Specific Building Enclosure Verification Program	Per Specifications	Specific to WRB: Three alternatives for compliance with QAP	Case Study Project: Specifications did not include performance testing of WRB
QC Checklists	Yes	No	
No	No	Specific testing required for WRB	
Building Enclosure maintenance manual, preventative maintenance program	No	No	
Schedule of service during warranty phase, call-back and warranty Enforcement	Yes	No	

# HCMC by the Numbers

- \$950 million annual budget
- 620,781 clinic visits
- 486 staffed hospital beds
- 23,051 inpatients treated
- 112,626 emergency department & urgent care visits
- 2,243 births per year
- Paramedics serve residents in 14 cities in Hennepin County
- Approximately 50% of Minnesota's physicians have trained at HCMC
- Minnesota's only 24/7 Hyperbaric Chamber



# Case Study: HCMC Clinic and Specialty Center



Houses 37 clinics previously in 9 buildings

337,000 SF clinic space

200 space underground parking

Skyway and tunnel connection to HCMC Campus

Primary Care and Specialty Clinics

- Same day surgery and procedure
- Comprehensive Cancer Center with radiation therapy
- Physical Therapy and Rehabilitation
- Outpatient Imaging and Women's Imaging
- Traumatic Brain Injury Center
- Integrative Health

# Strategies: Project Quality Plan (PQP)

## Personnel



Scope Manager



## Product




## Process




Last Planner Method



# Strategies: Project Quality Plan (PQP)



# Case Study: HCMC Clinic and Specialty Center




## Building Construction:

Cast-in-place concrete structure

Light gauge framing exterior wall construction

Exterior finish materials:

- Precast panels (ven
- Metal panels on up
- Curtainwall system



# Design Review: The Building Membrane

## Prescriptive Specification

- Multiple manufacturers plus “others as approved”
- ASTM E2178 (max. 0.004 CF/minute/SF at 1.57 PSF differential pressure)
- $< 0.1$  Perm (vapor impermeable)
- Either self-adhering sheet or liquid-applied membrane

## Coordination with Other Trades

- Foundation waterproofing material: Use same manufacturer
- Sealant compatibility at curtainwall
- Construction Sequencing



air barrier  
**abaa**  
association of  
america



bbc.com




## Walls Containing Mineral Wool Insulation

Wall Component	Materials
<b>Base wall system – Use either 1, 2, 3, 4 or 5</b>	<ul style="list-style-type: none"> <li>1 – Concrete wall</li> <li>2 – Concrete Masonry wall</li> <li>3 – Standard Clay Brick Wall</li> <li>4 – Adobe Block Wall</li> <li>5 – 1 layer – ½-inch thick, Type X, Gypsum wallboard on interior, installed over steel studs: minimum 3 ½-inch depth, minimum 20-gauge at a maximum of 16-inch OC with lateral bracing every 4 ft. vertically</li> </ul>
<b>Cavity Insulation – Use either 1, 2 or 3</b>	<ul style="list-style-type: none"> <li>1 – None</li> <li>2 – Fiberglass batt insulation (faced or unfaced)</li> <li>3 – Any noncombustible insulation</li> </ul>
<b>Exterior sheathing – Use either 1, 2 or 3</b>	<ul style="list-style-type: none"> <li>1 – None</li> <li>2 – ½-inch thick, exterior type gypsum sheathing</li> <li>3 – ½-inch thick, Type X, exterior type gypsum sheathing</li> </ul>
<b>Air and water barrier applied to gypsum sheathing – Use either 1, 2, 3, 4, 5, 6, 7, 8 or 9</b>	<ul style="list-style-type: none"> <li>1 – Perm-A-Barrier® Liquid</li> <li>2 – Perm-A-Barrier® NPL</li> <li>3 – Perm-A-Barrier® NPL 10</li> <li>4 – Perm-A-Barrier® VPO</li> <li>5 – Perm-A-Barrier® VPL</li> <li>6 – Perm-A-Barrier® VPL LT</li> <li>7 – Perm-A-Barrier® Wall Membrane</li> <li>8 – Perm-A-Barrier® Aluminum Wall Membrane</li> <li>9 – Perm-A-Barrier® VPS</li> </ul>
<b>Exterior insulation</b>	<p>Mineral wool (2" min. thick, unfaced, mechanically attached and meets ASTM C612).</p> <ul style="list-style-type: none"> <li>1 – The mineral wool shall not have any type of facer on either side.</li> <li>2 – The mineral wool shall be noncombustible via ASTM E 136 testing. The density of the mineral wool shall range from 4.0 to 9.0 lbs/ft<sup>3</sup>. The R-value/inch of the mineral wool shall range from 3.5 to 4.5.</li> <li>3 – The mineral wool insulation must be mechanically attached.</li> <li>4 – The mineral wool must completely cover the air barrier.</li> </ul>
<b>Exterior Veneer – Use either 1 or 2</b>	<ul style="list-style-type: none"> <li>1 – Any noncombustible exterior veneer with or without air gap between exterior insulation and exterior veneer</li> <li>2 – Any combustible exterior veneer, that has been successfully tested by the panel manufacturer via NFPA 285 test method, with or without air gap between exterior insulation and exterior veneer. Installed using standard installation techniques. Evidence of testing in accordance with NFPA 285 and/or an ICC-ES report must be submitted to the code official.</li> </ul>

# Design Review: The Building Membrane

Gypsum Sheathing

← Gauge metal window support




# Design Review: The Building Membrane

Gypsum Sheathing

WRB flashing at jambs,  
sill, and head

Stretch wrap at corners



# Design Review: The Building Membrane



air barrier

**abaa**

association of  
america


# Design Review: The Building Membrane




## Compatibility with other materials

- Must still meet specification requirements
- Must also meet project documentation requirements
  - Submittal
  - Substitution request
- Needs to address legitimate concern
- Compatibility letter both ways


# Design Review: The Building Membrane



# Design Review: The Building Membrane



# Strategies: Project Quality Plan (PQP)






# Strategies: Project Quality Plan (PQP)

## Personnel




## Product




## Process






## Enclosure Review Findings

- Discontinuous air barrier
- Drainage at precast
- Thermal bridge
- Construction Sequence:  
Sealing Air Barrier  
Drainage Channel / Tubes




INTERIOR

EXTERIOR




## Enclosure Review Findings

- Discontinuous air barrier
- Thermal bridge
- Movement joint locations
- Construction sequence



## Modified Detail

- Continuous air barrier
- Thermal bridge
- Movement joint locations
- Construction sequence




## Enclosure Review Findings

- Potential collection area / leak
- Construction Sequence

## EXTERIOR


## INTERIOR



## Modified Detail


- Simplified air barrier, same as the rest of the building
- Simplified expansion joint
- Construction sequence

**STEP 1**







STEP 2




STEP 3




STEP 4




**STEP 5**




**STEP 6**




**STEP 6a**



STEP 7





STEP 7a







# Physical Mockup




# Physical Mockup




4 Front Side View  
Z001 1/4" = 1'-0"



6 Section 1  
Z001 1/2" = 1'-0"



7 Section 2  
Z001 1/2" = 1'-0"



8 Section 3  
Z001 1/2" = 1'-0"

# Physical Mockup




# Physical Mockup




## Lessons Learned

- First test of revised precast back-up wall system
- Increased gauge of sheet metal plate frame around windows
- Expansion joint transition at vertical slot windows
- Sequencing of precast and second level stud framing
- Eliminated redundant detail membrane at window sill

# Strategies: Project Quality Plan (PQP)



# Strategies: Project Quality Plan (PQP)




# Inspections



air barrier  
**abaa**  
association of  
america

# Inspections

air barrier  
**abaa**  
association of  
america





# Inspections



air barrier  
**abaa**  
association of  
america

# Inspections



# Inspections

## BRAUN INTERTEC

### Enclosure Observation Daily Report

Report No.:	#02	Date of this Report:	09/21/2016	Braun Project No.:	B1601432
Project Name:	HCMC AOSC, Minneapolis, MN				
Client:	Mortenson Construction	Workers:			
Braun Project Mgr.:	Jack R. Rasmussen	Temp/Weather:	68 degrees, mostly cloudy, 10 mph east winds		

Type of Observation:	Location of material:	Manufacturer:	Type of Material:
<input type="checkbox"/> Continuous	<input type="checkbox"/> Roofing		
<input checked="" type="checkbox"/> Periodic	<input type="checkbox"/> Wall Panels		
	<input type="checkbox"/> Pre-Cast Panels		
	<input type="checkbox"/> Windows	EFCO	5600 Series Curtain Wall
	<input type="checkbox"/> Air Barrier	Grace	Perm-A-Barrier (Self-Adhered)
	<input type="checkbox"/> Waterproofing	Grace	Procor

#### Description and location of work completed and list tests performed :

We observed the following area(s) of work:

- First floor around building perimeter.
- Window openings on the second floor

Type of Work Observed:

- Exposed top edge of waterproofing system above backfilled soil
- Self-adhered weather barrier installation
- Pre-cast veneer installation
- Curtain wall framing

Status of previous discrepancies: (Strike through indicates corrections completed) (Bold is additional comment)

- ~~Plate at sill was trimmed and will not provide solid backing for the primary seal of the curtain wall. (Photo 11)~~
- ~~Huber Stretch Tape observed at sill to jamb transition without backing and prone to puncture. Opposite jambs were installed with Grace SA Membrane and then wrapped in Huber Stretch Tape providing more durable installation. (Photo 12)~~
- ~~Tear in waterproofing observed at pre-cast panel installation requiring patching/repair. (Photo 13)~~
- ~~At curved wall, waterproofing installed prior to the precast panels minimally extends beyond the face of the panel. Care will be required with limited ability to tie the horizontal waterproofing together at this location. (Photo 14)~~
- ~~Note observed in Huber Stretch Tape at sill/jamb condition. (Photo 15)~~
- ~~Detail 6H/546 shows a drip flashing at the bearing ledge and the weather barrier lapping onto it protecting the floor slab edge. The membrane in place terminates onto the concrete vertical without drip flashing. When installed, the membranes and flashings should be in single lap fashion to direct water out of wall assembly. (Photo 16)~~



Photograph 1

Overview of west elevation.



Photograph 2

Curtain wall framing at north elevation.



Photograph 3

Overview of east half of north elevation.




Photograph 4

Partial east elevation viewed from north.

# Inspections



# Strategies: Project Quality Plan (PQP)




# Strategies: Project Quality Plan (PQP)

## Personnel



## Product



## Process



WEST ELEVATION				SOUTH ELEVATION				EAST ELEVATION				South Expansion								
LEVEL 7 WEST ROOF				PENTHOUSE ROOF				NORTH EAST CORNER		EAST		SOUTH								
LIFT NORTH	LIFT SOUTH	MISC		SWING 1	SWING 2	SWING 3	SWING 4	LIFT	SWING 4	LIFT		SWING 1	SWING 2	LIFT @ CORNER	SWING 3	LIFT		LIFT	LIFT	
Deck 1 11.7.1E	WINDOW TRIM M <sub>0</sub> GRATH			Deck 1 11.7.1E	MEMBRANE OLYMPIC							Deck 1 11.7.1E						Deck 1 11.7.1E		
Deck 2 11.8.1E	WINDOW TRIM M <sub>0</sub> GRATH			Deck 2 11.8.1E	MEMBRANE OLYMPIC							Deck 2 11.8.1E						Deck 2 11.8.1E		
Deck 3 11.9.1E	2 FURRING / INSULATION OLYMPIC			Deck 3 11.9.1E	WINDOW TRIM M <sub>0</sub> GRATH							Deck 3 11.9.1E						Deck 3 11.9.1E		
Deck 4 11.10.1 E	2 FURRING / INSULATION OLYMPIC			Deck 4 11.10.1 E	WINDOW TRIM M <sub>0</sub> GRATH							Deck 4 11.10.1 E						Deck 4 11.10.1 E		
Deck 5 11.11.1 E	2 FURRING / INSULATION OLYMPIC			Deck 5 11.11.1 E	WINDOW TRIM M <sub>0</sub> GRATH							Deck 5 11.11.1 E						Deck 5 11.11.1 E		
Deck 6 11.14.1 E	MOVE SWING 1 TO SWING 2 SOUTH		2 FURRING / INSULATION OLYMPIC	Deck 6 11.14.1 E	MOVE SWING 1 WEST TO SWING 2 SOUTH							Deck 6 11.14.1 E	INSTALL SWING 1 EAST M <sub>0</sub> GRATH	INSTALL SWING 2 EAST M <sub>0</sub> GRATH		INSTALL SWING 3 EAST M <sub>0</sub> GRATH	INSTALL SWING 4 EAST M <sub>0</sub> GRATH	Deck 6 11.14.1 E		
Deck 7 11.15.1 E	MOVE SWING 1 TO SWING 2 SOUTH		2 FURRING / INSULATION OLYMPIC	Deck 7 11.15.1 E	MEMBRANE OLYMPIC							Deck 7 11.15.1 E	INSTALL SWING 1 EAST M <sub>0</sub> GRATH	INSTALL SWING 2 EAST M <sub>0</sub> GRATH		INSTALL SWING 3 EAST M <sub>0</sub> GRATH	INSTALL SWING 4 EAST M <sub>0</sub> GRATH	Deck 7 11.15.1 E		
Deck 8 11.16.1 E			2 FURRING / INSULATION OLYMPIC	Deck 8 11.16.1 E	MEMBRANE OLYMPIC							Deck 8 11.16.1 E		INSTALL SWING 2 EAST M <sub>0</sub> GRATH		INSTALL SWING 3 EAST M <sub>0</sub> GRATH	INSTALL SWING 4 EAST M <sub>0</sub> GRATH	Deck 8 11.16.1 E		
Deck 9 11.17.1 E			2 FURRING / INSULATION OLYMPIC	Deck 9 11.17.1 E	MEMBRANE OLYMPIC	MOVE SWING 2 WEST TO SWING 3 SOUTH						Deck 9 11.17.1 E						Deck 9 11.17.1 E		
Deck 10 11.18.1 E			2 FURRING / INSULATION OLYMPIC	Deck 10 11.18.1 E	MEMBRANE OLYMPIC	MOVE SWING 2 WEST TO SWING 3 SOUTH						Deck 10 11.18.1 E						Deck 10 11.18.1 E		
3-M <sub>0</sub>	METAL PANELS M <sub>0</sub> GRATH	2 FURRING / INSULATION OLYMPIC		3-M <sub>0</sub>	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH			3-M <sub>0</sub>	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH				3-M <sub>0</sub>		
6-M <sub>0</sub>		2 FURRING / INSULATION OLYMPIC	METAL PANELS M <sub>0</sub> GRATH	6-M <sub>0</sub>	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH			6-M <sub>0</sub>	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH				6-M <sub>0</sub>		
7-M <sub>0</sub>		2 FURRING / INSULATION OLYMPIC	METAL PANELS M <sub>0</sub> GRATH	7-M <sub>0</sub>	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	2 FURRING / INSULATION OLYMPIC		7-M <sub>0</sub>	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH				7-M <sub>0</sub>		
8-M <sub>0</sub>		2 FURRING / INSULATION OLYMPIC	METAL PANELS M <sub>0</sub> GRATH	8-M <sub>0</sub>				METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	2 FURRING / INSULATION OLYMPIC		8-M <sub>0</sub>	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH				8-M <sub>0</sub>		
3-M <sub>0</sub>			METAL PANELS M <sub>0</sub> GRATH	3-M <sub>0</sub>				METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	2 FURRING / INSULATION OLYMPIC		3-M <sub>0</sub>	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	2 FURRING / INSULATION OLYMPIC			3-M <sub>0</sub>		
18-M <sub>0</sub>			METAL PANELS M <sub>0</sub> GRATH	18-M <sub>0</sub>				METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	2 FURRING / INSULATION OLYMPIC		18-M <sub>0</sub>	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	2 FURRING / INSULATION OLYMPIC			18-M <sub>0</sub>		
13-M <sub>0</sub>			METAL PANELS M <sub>0</sub> GRATH	13-M <sub>0</sub>						METAL PANELS M <sub>0</sub> GRATH		13-M <sub>0</sub>	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	2 FURRING / INSULATION OLYMPIC	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	13-M <sub>0</sub>		
14-M <sub>0</sub>	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH		14-M <sub>0</sub>						METAL PANELS M <sub>0</sub> GRATH		14-M <sub>0</sub>	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	2 FURRING / INSULATION OLYMPIC	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	14-M <sub>0</sub>		
15-M <sub>0</sub>	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH		15-M <sub>0</sub>						METAL PANELS M <sub>0</sub> GRATH		15-M <sub>0</sub>	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	2 FURRING / INSULATION OLYMPIC	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	15-M <sub>0</sub>		
16-M <sub>0</sub>	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH		16-M <sub>0</sub>	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH			METAL PANELS M <sub>0</sub> GRATH		16-M <sub>0</sub>			2 FURRING / INSULATION OLYMPIC	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	16-M <sub>0</sub>		
17-M <sub>0</sub>	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH		17-M <sub>0</sub>	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH		METAL PANELS M <sub>0</sub> GRATH		17-M <sub>0</sub>			2 FURRING / INSULATION OLYMPIC	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	17-M <sub>0</sub>	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH
28-M <sub>0</sub>	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH		28-M <sub>0</sub>	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH		28-M <sub>0</sub>			2 FURRING / INSULATION OLYMPIC	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	28-M <sub>0</sub>	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH
21-M <sub>0</sub>			WINDOW PANELS M <sub>0</sub> GRATH	21-M <sub>0</sub>	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH		21-M <sub>0</sub>			2 FURRING / INSULATION OLYMPIC	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	21-M <sub>0</sub>	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH
22-M <sub>0</sub>			WINDOW PANELS M <sub>0</sub> GRATH	22-M <sub>0</sub>	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH		22-M <sub>0</sub>			2 FURRING / INSULATION OLYMPIC	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH	22-M <sub>0</sub>	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH
23-M <sub>0</sub>			WINDOW PANELS M <sub>0</sub> GRATH	23-M <sub>0</sub>	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH			23-M <sub>0</sub>	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH		2 FURRING / INSULATION OLYMPIC	METAL PANELS M <sub>0</sub> GRATH	23-M <sub>0</sub>	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH
24-M <sub>0</sub>			WINDOW PANELS M <sub>0</sub> GRATH	24-M <sub>0</sub>				WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH			24-M <sub>0</sub>	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH		2 FURRING / INSULATION OLYMPIC	METAL PANELS M <sub>0</sub> GRATH	24-M <sub>0</sub>	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH
27-M <sub>0</sub>			WINDOW PANELS M <sub>0</sub> GRATH	27-M <sub>0</sub>				WINDOW PANELS M <sub>0</sub> GRATH				27-M <sub>0</sub>	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH		2 FURRING / INSULATION OLYMPIC	METAL PANELS M <sub>0</sub> GRATH	27-M <sub>0</sub>	METAL PANELS M <sub>0</sub> GRATH	METAL PANELS M <sub>0</sub> GRATH
28-M <sub>0</sub>				28-M <sub>0</sub>								28-M <sub>0</sub>	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH		2 FURRING / INSULATION OLYMPIC	METAL PANELS M <sub>0</sub> GRATH	28-M <sub>0</sub>		
23-M <sub>0</sub>				23-M <sub>0</sub>								23-M <sub>0</sub>	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH		2 FURRING / INSULATION OLYMPIC	METAL PANELS M <sub>0</sub> GRATH	23-M <sub>0</sub>		
38-M <sub>0</sub>				38-M <sub>0</sub>								38-M <sub>0</sub>	WINDOW PANELS M <sub>0</sub> GRATH	WINDOW PANELS M <sub>0</sub> GRATH		2 FURRING / INSULATION OLYMPIC	METAL PANELS M <sub>0</sub> GRATH	38-M <sub>0</sub>		




air barrier  
**abaa**  
association of  
america



EarthCam



# Testing: Windows and Curtainwall



# Testing: Windows and Curtainwall



# Testing: Windows and Curtainwall



# Testing: Windows and Curtainwall



Summary:

Robust on-site Quality Management program includes:

1. Have the right people in place

- Train and “deputize” the whole construction team
- Third Party reviewers
- Inspections and testing agencies

2. Manage the process

- Plan, Execute, Monitor/Control, Close
- Make sure changes are properly documented
- Use processes that add value
- Is risk being managed appropriately?
- Start early, talk quality often.
- Construction is a team sport

3. Review the documents

- Is it constructible?
- Are the details consistent?
- What areas need further study?
- What’s the goal?



# Chris Bubser

AIA, LEED-AP BD+C

Phone: 763-287-5971

E-mail: [chris.bubser@mortenson.com](mailto:chris.bubser@mortenson.com)

[www.mortenson.com](http://www.mortenson.com)



air barrier  
**abaa**  
association of  
america  
**CONFERENCE  
& TRADE SHOW**

MAY 8-9  
**2018**  
SALT LAKE  
CITY

AIR BARRIER EDUCATION TRACKS FOR  
THE CONSTRUCTION INDUSTRY